



Allstate/Encompass/National General Program Guidelines

Water Mitigation, Fire Mitigation and Asbestos Abatement Requirements	Timeline Requirements
Accept or Reject Xactimate Project	30 minutes from assignment received
Customer Contacted Timestamp	30 minutes from assignment received
Site Inspected Timestamp	4 hours from assignment received
Upload 24 Hour Report, Inspection Photos, Work Auth, Xactimate Sketch	24 hours from inspection
ClaimXperience Video 1 Pre mitigation (Mitigation only)	Complete during initial inspection, then upload into link found in XA upon initial estimate upload
Job Started Timestamp	When mitigation work begins
Job Completed Timestamp	When mitigation work is completed
ClaimXperience Video 2 Post mitigation (Mitigation only)	Before uploading completed estimate for CF review
Upload RMS estimate to Validate, reconcile violations and re-process in Validate	Before uploading completed estimate for CF Review
Upload Preliminary Xactimate Estimate & Supporting Documents for CF Review	5 days or less from assignment received
Upload of Revisions or Missing Documents, if requested by CF	24 hours from time of request
Tarping, Board-Up, and Asbestos Testing Requirements	Timeline Requirements
Accept or Reject Xactimate Project	30 minutes from assignment received
Customer Contacted Timestamp	30 minutes from assignment received
Site Inspected Timestamp	4 hours from assignment received
Upload 24 Hour Report, Inspection Photos, Work Auth, Xactimate Sketch	24 hours from inspection
Job Started Timestamp	When mitigation work begins
Job Completed Timestamp	When mitigation work is completed
Upload RMS estimate to Validate, reconcile violations and re-process in Validate	Before uploading Completed estimate for CF Review
Upload Final Xactimate Estimate & Supporting Documents for CF Review	5 days from assignment received
Upload of Revisions or Missing Documents, if requested by CF	24 hours from time of request
Contents Requirements (Pack Out, Cleaning, Inventory, Pack Back)	Timeline Requirements
Accept or Reject Xactimate Project	30 minutes from assignment received
Customer Contacted Timestamp	4 hours from assignment received
Request Scope	At time of customer contact
Site Inspected Timestamp	48 hours from assignment received
Upload 24 Hour Report, Inspection Photos, and Xactimate Sketch	24 hours from inspection
Job Started Timestamp	When contents work begins
Job Completed Timestamp	When contents work is completed
Upload RMS estimate to Validate, reconcile violations and re-process in Validate	Before uploading Completed estimate for CF Review
Upload Preliminary Xactimate Estimate & Supporting Documents for CF Review	8 days from assignment received
Upload of Revisions or Missing Documents, if requested by CF	24 hours from time of request
Reconstruction	Timeline Requirements
Accept or Reject Xactimate Project	30 minutes from assignment received
Customer Contacted Timestamp	4 hours from assignment received
Site Inspected Timestamp	48 hours from assignment received
Upload 24 Hour Report, Inspection Photos, and Xactimate Sketch	24 hours from inspection
Upload RMS estimate to Validate, reconcile violations and re-process in Validate	Before uploading Completed estimate for CF Review
Upload Preliminary Xactimate Estimate & Supporting Documents	5 days or less from assignment received
Upload of Revisions or Missing Documents, if requested by CF	24 hours from time of request



Allstate/Encompass/National General Program Guidelines

CONTENTS (CLICK ON SECTIONS BELOW TO JUMP)

CONTACT INFO – PROGRAM SUPPORT	3
PROGRAM OVERVIEW	3
PERFORMANCE WEIGHTED DISTRIBUTION	4
PERFORMANCE CONSULTANTS	4
SERVICE LEVEL AGREEMENT REQUIREMENTS	4
MICA MOBILITY & MICA SMARTAUDIT	5
VALIDATE	6
CLAIMXPERIENCE	7
PRE-APPROVALS	8
CARRIER COMMUNICATION	9
GENERAL REQUIREMENTS	10
WATER MITIGATION REQUIREMENTS	12
TARPING/BOARD-UP REQUIREMENTS	16
FIRE MITIGATION REQUIREMENTS	17
Asbestos REQUIREMENTS	17
CONTENTS REQUIREMENTS	19
DRYWALL & TEXTURE	23
PAINT	24
FLOORING	25
GENERAL RECONSTRUCTION REQUIREMENTS	27
ROOFING REQUIREMENTS	30
TREE & TREE DEBRIS REMOVAL	33
ICE DAMS & WINTERIZATION	33
ESTIMATE FEE SCHEDULE	33
DOCUMENTATION REQUIREMENTS	34
CF REVIEW CHECKLIST	37



Allstate/Encompass/National General Program Guidelines

CONTACT INFO – PROGRAM SUPPORT

Business Development

- For general program questions or feedback please contact Business Development:
 - Heather Bradley, VP Business Development
 - Phone: 904-899-6123
 - Email: HBradley@PaulDavis.com

Strategic Account Management

- For claim payment inquiries and capacity concerns, please contact Account Management:
 - Caroline Cundiff, Account Manager
 - Phone: 904-899-6118
 - Email: Caroline.Cundiff@pauldavis.com

Claims Force

- For estimating questions, please contact Claims Force:
 - Caleb Kinzler, Estimate Review Team Manager
 - Phone: 904-899-6243
 - Caleb.Kinzler@PaulDavis.com
 - Jimmy Reed, Director of Estimate Review
 - Phone: 904-899-6226
 - Email: Jimmy.Reed@PaulDavis.com

MICA/Validate Support

- For technical support with MICA or Validate, please contact CoreLogic (NextGear) Support:
 - Support
 - 866-769-7855
 - Email: support@nextgear.com
 - 24/7 Chat located in MICA & Validate

PROGRAM OVERVIEW

Services Offered

- Mitigation Water
 - Currently, mold is not a part of the GHRN direct program.
 - If you receive a loss with mold, the estimate should be sent directly to the adjuster.
 - To send the mold claim to Allstate utilize the email address claims@claims.allstate.com and include the claim number and insured name in the subject line.
 - In the body of the email indicate that the attached estimate is for Mold Remediation.
- Mitigation-Fire
- Mitigation-Other
- Tarping/Board Up
- Contents, Contents Cleaning, Contents-Pack Out, and Contents-Other
- Reconstruction

Indirect Assignments

- If an Allstate customer or Agent contacts your network or service provider direct and has (or intends to file) a claim with Allstate, you must notify us to receive an XactAnalysis assignment in your data set.
- If the customer does not have a claim, nor do they intend to file a claim, you do not need to contact Allstate Claims but are required to extend all contracted benefits to the customer/Agent.



Allstate/Encompass/National General Program Guidelines

XactAnalysis Assignments

- All work (direct assign through use of the GHRN Tool or Indirect Assignments) will require an assignment in XactAnalysis.
- Networks/Service Providers should not be creating these assignments and should notify Allstate Immediately.
- The proper assignment will be input, documented, and assigned – thereby acknowledging vendor involvement and providing appropriate direction before the job progresses.

PERFORMANCE WEIGHTED DISTRIBUTION

PWD Rankings

- Allstate configures distribution of assignments based upon performance in timely uploads in combination with Accuracy.
- There are 2 rankings: one is for mitigation and the other is for reconstruction assignments.
- The scores and rankings are calculated by state, not individual office or zip code.
- The upload speed is measured by time from Job Received as the start time and Estimate Marked Complete and uploaded into XA. Accuracy for mitigation is determined by Passthrough Percentage.
- Accuracy for Recon is determined by Reinspection scores.
- To determine the current Performance Weighted Distribution (PWD) score for your state, contact the Allstate Account Manager Caroline Cundiff.

PERFORMANCE CONSULTANTS

PC Support

- PC Support is available in your area to assist with escalated issues and review current performance.
- To locate your PC please visit the PC Market Map housed in the Teams channel for US Program Guidelines under Allstate Resources.
- You can also reach out to the Account Manager Caroline Cundiff for assistance setting up a meeting with your PC.

SERVICE LEVEL AGREEMENT REQUIREMENTS

Job Not Sold - Cancellation Request

- Do not use the Job Not Sold status when a site visit has occurred, and you will be uploading an invoice for the inspection.
- Job Not Sold (Request for Cancellation) – as soon as possible.
 - Use this Status Update if an assignment should be cancelled, include specific reason for cancellation.
 - You are required to call the carrier to inform them of the reason, and request they reassign loss to another vendor.

Rejection

- Reject from Xactimate – within 30 minutes of receiving the assignment.
 - Reject an assignment only when your office cannot accept an assignment due to inability to meet SLA requirements, insufficient capacity to handle the assignment, or other reasons not caused by the customer.
 - You are required to call the carrier to inform them of the reason, and request they reassign loss to another vendor.

Status Updates – XactAnalysis Notes

- Status updates must occur once every 7 days to document the current progress of the job.
- Use Public RMS notes to provide these updates.

Timestamps

- Use RMS timestamps in real time, to ensure the following timestamps are updated through the data integration with XactAnalysis.
 - Customer Contacted
 - Site Inspected
 - Job Started
 - Job Completed



Allstate/Encompass/National General Program Guidelines

PDRI Direct Program Warranty

- Good workmanlike manner, within industry standard performance for service, which applies to any subcontractor as well.
- We uphold services provided following proper laws, regulations, and maintain necessary security standards.
- Most effective process, equipment, and technology will be utilized and performed for each Allstate (or Allstate company) assignment, with IICRC/industry standard trained professionals.
- Warranty, for Allstate and direct Allstate customer will be effective for a period of five (5) years from the earlier of the date of completion, or the date upon services substantially completed, and one (1) year for materials.

MICA MOBILITY & MICA SMARTAUDIT

MICA Mobility

- MICA Mobility is required to be used on all Allstate mitigation assignments.
- All Mitigation – Water and Fire – Other assignments in XactAnalysis (related to a water peril) will require the use of MICA Mobility for recording Job Information related (but not limited) to:
 - Contact and inspection dates and times
 - Category, Class and source of water
 - Equipment set up, takedown and monitoring.
 - Drying Logs
 - Temperature/Humidity readings inside/outside as well as the air going into and out of the dehumidifier.
 - Grains per pound as well as grain depression
 - Equipment utilization should be properly reflected to the nearest tenth of a day in Xactimate.
 - The type of meters used to determine moisture content.
 - Daily readings from dehumidifiers
 - Drying goal (percent or pints) of affected materials
 - Completion of onsite mitigation services
- Any assignments uploaded without MICA Mobility API data will not be reviewed by Claims Force until reconciled.

MICA Details Report

- The Details Report is the drying document within MICA that the Claims Force Team and Allstate uses to review the claim.
- Whenever you have made changes to your drying logs and/or added any new photos in MICA a new Details Report should be created.
- How to Create a Details Report in MICA
 1. In the MICA assignment navigate to Reports tab located in the blue ribbon.
 2. Click on Create Detail Report

MICA SmartAudit

- MICA SmartAudits will be completed automatically once a mitigation estimate is QA Approved
- If the SmartAudit identifies changes or support needed, the estimate will be auto rejected from the carrier.
- It is the office's responsibility to review the rejection and SmartAudit findings and make the necessary changes.

Correct MICA Loss

- Ensure you have only 1 assignment in MICA for your Water Assignments.
- There may be times when you have started an assignment in MICA before you received the assignment that is linked to XA.
- Please make sure that you merge the assignments in MICA as this can cause the drying data to not be available and can lead to issues with linking the assignment to RMS.

Merge Losses in MICA

- Occasionally there may be a time when you come across multiple of the same claim within MICA.
- This can occur when a project is initiated locally through MICA and then after the project is started an assignment is issued by a carrier or other outside source.
- When this occurs, it is best to merge the claims together.
 1. From within MICA Web select Loss Search in the upper left corner.



Allstate/Encompass/National General Program Guidelines

2. Search by Owner Name, Claim # or other common criteria between the claims.
 3. Select Search.
 4. Claims with the same search criteria will now appear on your screen.
- It is important to identify which claim to use to initiate the merge.
 - Locate the claim that is NOT linked to other applications (DASH, XactAnalysis etc.) as indicated with the application's logo in the section below.

Initiating the Merge

1. Using the claim that you determined in the above step, select the Merge link on the right of the page.
2. In the new window the duplicate claim will appear. Select Merge
 - NOTE: If you do not see the duplicate claim appear, search for it using the fields at the top
3. Select OK to confirm the merge.
 - IMPORTANT NOTE: Once a claim is merged it cannot easily be unmerged. Please contact the MICA Support team for questions or issues related to merging.
4. After confirming the merge, you will be returned to the Search Loss(es) window in MICA. You should notice the one remaining claim containing merged data from the original two projects.
5. Review the merged data in the claim.

VALIDATE

Requirement

- Validate is required by Allstate to be used both for the pre-scrub process and by the Claims Force Team to complete the final approval of every estimate.
- Failure to use Validate for the pre-scrub, revisions, and re-scrub process will result in a delayed Claims Force review and approval.

Process

- There are 6 primary steps for using Validate to review estimates:
 - Initiate audit from the estimating platform
 - X1 - Create Rough Draft
 1. Navigate to the Xactimate project and click on Documents from the left menu.
 2. Select Reports.
 3. In the Report section use the drop down to select Rough Draft
 4. Check each box on the left under Print Selection.
 5. Do not check any boxes on the right under Additional Options.
 6. Press Export and save the copy of the Rough Draft to your computer.
 - X1 – Upload Estimate in RMS
 1. Navigate to RMS and locate the appropriate job.
 2. Select Upload Estimate in the Accounting Information quadrant.
 3. At Estimate PDF Type select the radio button for Rough Draft PDF.
 4. At Data Estimate & Final Draft click Select and attach your saved estimate from your device to both locations.
 5. Check the box to Submit to Validate
 6. Press Upload Estimate.
 - For Water Mitigation: If you have NOT used MICA mobility you will need to select the Category and Class of the loss. If any other division, you can leave these as N/A
 - For Reconstruction: Finish the entire Validate review process using the Rough Draft PDF, then use Vendor Exchange to import your Estimate for creating the Work Orders
 - Launch Review from within the RMS Estimate Tracker
 1. Navigate to RMS and locate the appropriate job.
 2. Select Estimate Tracker in the Accounting Information quadrant.
 3. In the Estimator Tracker click on Review Violations to launch the Validate window.
 4. The Validate review will now open.
 - Review & explain the estimate Review and explain all opportunities in Validate
 1. Select the Explain Button next to the line item you would like to explain.

Allstate/Encompass/National General Program Guidelines

2. Use the radio button next to the best explanation option as it relates to your estimate and line item.
3. Include a note when required or appropriate.
4. Select Done to save your inputs.
5. Repeat until all exceptions have been addressed.
 - Exceptions are indicated in the estimate with red text.
 - Every red text exception should be addressed by one of the available explanation options.
 - Exceptions can be associated to a specific line item(s) or related to equipment in MICA.
 - Aim for 100! The speed dial on the top right corner will indicate the score of the estimate. The score goal is 100 which will be reached when the estimate is uploaded with no exceptions or when any exceptions that remain have been explained in your review.
 - Each claim should have at least 2 Estimates uploaded; however, you may upload as many different versions of the estimate as needed.
- Make updates in estimating platform, correct or update any necessary changes.
 1. As soon as you complete the estimate in Validate you should simultaneously be making the necessary adjustments that you had marked "Will Change in Estimate" within the estimate in the appropriate estimating platform.
 2. You can use the Filter By setting reviewed below to view just the "Will Change in Estimate" items.
- Upload corrected estimate from the estimating platform.
 1. Repeat the steps in this guide to upload and review a second estimate.
 2. Initiate Audit, Launch Review, Review and Explain Estimate for the second review.
 - Items explained in the first review will not need to be explained again; however, if there are any additional flags, use the Filter By drop down to view any new exceptions.
- Finalize Estimate, update the Xactimate status.
 1. From within the estimate in Xactimate select Complete.
 2. Select Mark Complete.
 3. Await Claims Force Review

CLAIMXPERIENCE

Requirements

- Please reach out with any questions to Account Manager, Caroline Cundiff: Caroline.Cundiff@pauldavis.com
- It is mandatory to use the ClaimXperience link on water and fire mitigation assignments.
 - Uploading requested videos is intended to aid with prompt damage assessment.
- Please educate your teams to be aware of this requirement and ensure they are utilizing the ClaimXperience videos.
- Allstate will reject Mitigation Water estimates without the required uploads and may also suspend for failure to comply.
- ClaimXperience is a tool (link inside of Xact) to facilitate communication and video collaboration between GHRN vendors and Allstate.
- Approval is still needed **prior** to work being completed.
- Approval shall be requested while **onsite** (at the loss location) to facilitate virtual collaboration with the IT.
- Pre-approvals need to be documented within XA showing the person providing approval, the date and the outcome.

Process

- ClaimXperience is started by the Inside technician (IT) and a link will be sent for upload in that specific platform.
- The link is found in Xact Analysis (XA) notes.
 - It should be copied and pasted into your browser address bar for use.
 - The link will be in notes within 2 hours of receiving the assignment and be available by the time you arrive onsite.
 - If the link is not available, please call the IT and request the link.
- Videos should be completed even if you have not received the link yet.
- The requirement is to upload 2 videos for each assignment using the same ClaimXperience link:
 - Initial Onsite Inspection - The first video should start the video recording at the source of the loss and then go to each room where there is potential damage. o All areas that have continuous flooring must be recorded in the video.
 - Please walk through all the damages and verbalize the mitigation plan. Announce the room you are walking into as you are walking through the mitigation plan, i.e., Kitchen, ceramic tile floors, cabinets reading XX moisture, etc.
 - Follow this process in each damaged room or rooms with continuous surfaces.
 - The second video should show any tear out that was completed (i.e., cabinets, drywall, etc.)
- Technicians do not need to measure during the video.



Allstate/Encompass/National General Program Guidelines

- Videos are for an overview of the mitigation plan, scope of damages and overview of post mitigation/demo.
 - videos should be no more than 2 – 2.5 minutes

Video Upload Requirements

- You must notify the customer that you are recording a short video that you will submit to Allstate
- If the customer instructs you not to record a video, then you should notify them that this is required by their carrier
- If the customer refuses the recording, please call the IT hotline to notify them and ensure you note the job file

PRE-APPROVALS

Pre-Approvals Required

- After Hours Emergency Service Call
 - Service calls occurring after hours will be reviewed on a case-by-case basis.
 - File notes will indicate time of receipt and onsite inspection, as well as reasons supporting deviation from standards.
 - ITs will determine if appropriate upon review of the estimate submitted in XactAnalysis.
- Asbestos Testing
 - No preapproval for standard testing shall be required.
 - Per Sample testing should be invoiced using proper Xactimate line items.
 - Any Full-Service Surveys shall be pre-approved by an IT.
- Flooring Removal
 - Carpet and Laminate flooring damaged by water will no longer require pre-approval.
 - Only affected areas should be removed; a sample retained for testing; and an ITSL submitted where appropriate.
 - Photo documentation of the damage and need to remove will be required.
- Specialty Trades
 - Pre-approval is not required for use of specialty trades up to \$300 when utilized to facilitate immediate drying and repairs or retain habitability of the home.
 - File should be properly documented for IT review.
- Tear Out and Removals
 - No pre-approval is required when removing affected carpet, door trim or laminate flooring affected by CAT 3 water.
- Specialty Equipment
 - Pre-approval is not required for use of one AFD during tear out of materials, or up to 2 days for CAT 3 losses.
 - Any use beyond these allowances requires pre-approval.

Pre-Approval Summary

- The following provides a summary of all items where Inside Technician/Adjuster approval is needed before work is performed.
- XactAnalysis notes will be updated by the network and the Inside technician/Adjuster at time of approval.
- Contact Inside Technician or Adjuster and request a Direct Connect code for virtual collaboration using Claim X®, if necessary.
- If attempting to reach an Inside Technician or Adjuster and no response is provided within 24 hours, you should escalate to the secondary approver (adjuster or IT), or GHRN CSL for assistance.
- Once pre-approval is received, the full name (first and last) of the Allstate approver should be documented in the XA notes for reference when reviewing for payment.
- Please note that all requests related to preapprovals require IT approval in the job file

Approval	Inside Technician (IT)	Adjuster (Claim Handler)	Description
Asbestos Abatement	X	X	Required when asbestos containing materials have been confirmed and the materials need to be removed for effective drying.
Asbestos Testing	X		Request approval for testing materials damaged by the loss we cover and suspected of containing asbestos fibers which may become friable. Contact GHRN Team to Request Assignment – Adjusters cannot create Asbestos Assignments.
Cabinet Pull	X		Contact Inside Technician to discuss direction and approval to remove cabinet or countertops. Request a Direct Connect code for



Allstate/Encompass/National General Program Guidelines

			virtual collaboration using ClaimXperience®, where appropriate. Photos are required and any faces, frames and doors should be carefully labeled and secured; and set aside for reinstallation and evaluation of quality.
Contents	X	X	Discuss damages and align on proper handling of the cleaning. If contents cleaning is approved, a separate XactAnalysis assignment will be created and assigned.
Number of Days Drying	X		If drying will exceed 4 days, contact the GHRN Team to discuss and document alignment. NOTE: Approvals to be obtained from the IT. Approvals by anyone other than an IT will be at the sole discretion of the reviewer.
Flooring Removal	X		Approval is required prior to removal of wood flooring (solid or engineered), ceramic tile and stone flooring. Pre-Approval is not needed for carpet or laminate flooring affected by water where damage is supported with photos in the file. Only affected area of flooring should be removed and sample left on site for proper valuation and possible submission to ITEL.
Specialty Trades	X		Pre-approval is needed when specialized work is performed and expected to exceed \$300 (electrical, plumbing, HVAC, etc.).
Mold (Testing or Remediation)	X	X	Contact should be made immediately to advise of mold >10SF. Pre-approval for testing and removal is required as most policies are limited in coverage for resulting mold damage.
Pack Outs	X	X	Approval is needed when contents cannot be manipulated and requires pack out or onsite storage (POD). If approved, a Contents Cleaning assignment will need to be created and assigned in XactAnalysis.
Tear Outs & Removals	X	X	Approval is needed when cabinets, door casings, countertops, bathtubs, etc. may need to be removed. Pre-Approval is not needed when removing carpet, door trim or laminate flooring affected by Cat 3.
Specialty Equipment	X		Approval is needed for alignment on specialty drying equipment (heated drying, floor mats, AFDs, etc.). Pre- Approval is not needed if invoicing for one AFD during one day of tear out; or up to 2 days for one AFD on a Cat 3 loss.

**If primary approver is not available (i.e., weekends, after hours) then approval from Adjuster/Claim Handler on duty should be documented in XactAnalysis*

CARRIER COMMUNICATION

Contact Allstate Immediately If...

- Uninhabitable/Partial Loss of Use
 - If during emergency services or reconstruction, the home is not functional/uninhabitable due to the loss, notify the Inside Technician/Adjuster.
 - Do not discuss habitability or ALE with the insured – this is the adjuster’s role.
- Coverage Concerns
 - Contact the Claim Handler (identified in the initial assignment notes in XA) regarding any issues involving potential pre-existing damages, long term or repeated seepage, concerns with habitability, vacancy, etc.
 - These situations may impact coverage and the Claim Handler is responsible for coverage determinations.
 - Evidence of ongoing damage
 - Evidence of prior damage
 - Any other information/observations which might present coverage concerns.
- Virtual Collaboration via Direct Connect code can be used to notify the Adjuster in any/all of these situations.

Cancellation of Assignments

- The Claim Handler is the first point of contact.



Allstate/Encompass/National General Program Guidelines

- For After Hours assistance, please email PropertyInsideTechnicianInquiries@allstate.com using the template provided in the Bulletin sent 2/2/22.

Coverage Concerns

- Contact the Claim Handler regarding potential coverage issues (ex: pre-existing damages, long term/repeated seepage, habitability, vacancy, etc.)

Mitigation Pre-Approval Request

- Check the estimating guidelines first and then call the IT Hotline (480-977-4880) for approvals as specified.
- Please document in XA with the first and last name of the person you spoke with and the specific approvals they granted.

Requesting Claim Owner Name and Contact Information

- XactAnalysis provides the Claim Handler name and contact.
- The note may show Claim Handler as "Allstate Claim" and provide 1-800-255-7828 as the contact number.
- If you need Claim Handler information, please call that number for assistance.

Restoration Approval Request

- Check the estimating guidelines first and contact the assigned reviewer for approvals as specified.
- If no reviewer assigned, call the IT Hotline.
- Please document in XA with the first and last name of the person you spoke with and the specific approvals they granted.

GENERAL REQUIREMENTS

Supporting Your Scope

- A labeled photo must be provided to support every line item in your estimate.
- O&P must be clearly supported through written commentary for every estimate it is applied to.
- Pre-approvals must be clearly documented in line-item notes for all scope that requires pre-approval.
- Reconstruction estimates cannot be QA Approved until:
 - Validate Prescrub (Instant Review & Revisions) is completed before upload to XactAnalysis.
 - All required supporting documents are uploaded.
 - Adequate commentary is included in estimate, 24-hour report, and XactAnalysis notes.
 - If full-service, the mitigation estimate is fully reconciled and QA Approved
 - This prevents overlap with the mit scope and ensures that scope of work and quantities match.

Estimate Pricelist

- Use the Checkpoint Price List for all estimates.
- If a supplement is required, the initial pricelist should be utilized and not updated.

Estimate Structure

- Ceiling – Walls – Floor (exterior = Roof – Siding – Ground); or
- Floors – Walls – Ceiling (exterior = Ground – Siding – Roof)

Content Manipulation

- Can be considered when repairs involve significant replacement of flooring, drywall/plaster, or when texturing ceiling or wall surfaces.
- Only 1 manipulation charge should be used per room, based on its size and quantity of contents.
- Contents manipulation hourly charges are not allowed.
- The following should be utilized when CON ROOM or WTR BLK apply:
 - Small room is Less than 100 SF.
 - Medium size room is 100-150 SF.
 - Large size room is 150-200 SF.
 - X-Large size room is 200+ SF.
- If less than the full room is affected and does not require manipulation, move out or blocking, the room size quantities should be adjusted accordingly (i.e., qty .25, .50, .75).



Allstate/Encompass/National General Program Guidelines

- If the room contains an excessive quantity of contents to be moved to facilitate proper drying or repairs, it is acceptable to adjust quantities to reflect this (1.10, 1.25, 1.50, etc.).
 - Photo documentation and F9 notes in Xactimate will be required to support quantities in excess of 1.
- If the room contains specialty contents items (Pianos, curio cabinets, aquariums, pool tables), please reach out to IT or adjuster for direction.
- F9 notes are needed to explain what contents are required to be moved
 - Example of required Xactimate F9 detailed note:
 - Medium size room: Bunk beds that were disassembled (2 people) 2 five draw dressers, 1 nightstand, 6 plastic bins stored under bunk bed, all items in the closet including boxes, clothes, shoes and some sports equipment moved to the garage area to be temp stored.

Deductible

- Amount of the deductible should be applied when directed to do so by the Inside Technician or Adjuster.

General Category Room

- A “General” category room should be created and used to place all “general” category line items that apply to the entire job.
 - Do not create an actual “general” room on the sketch.
- Some examples of general category line items are (including, not limited to):
 - Emergency Service Call
 - Equipment setup, take down, monitoring
 - Content Manipulation
 - PPE
 - HEPA filters
 - Debris Haul
 - Bid items for Subcontractor invoices

Header Information

- Paul Davis Logo
- Complete Office Name (“Paul Davis of...”)
- Office Address
- Email Address
- Office Phone Number and Fax Number
- Franchise Code/ID – must be included to properly route payment.

Labor Hours

- Labor hours should only be used if a specific Xactimate line item does not exist for the operation performed.
- Include a detailed line item note to provide explanation operations completed during labor hours listed.
- Provide detailed photos to provide support.

Opening Statement

- Do not include an opening statement – there should be no wording included.

Closing Statement

- The state specific Closing Statement must be applied to every estimate.
- Verisk has added default statements for every state that will meet Allstate’s compliance standards.

Demolition

- When estimating to selectively remove individual damaged items, the Xactimate removal or remove/replace line item should be used.
- If estimating the removal of all components of a room, the Xactimate demolish/remove room line items should be used.
- If estimating the demolition of an entire structure, the demolish/remove home may be appropriate.
- Document the Notes in XactAnalysis if there is any deviation from this standard.



Allstate/Encompass/National General Program Guidelines

WATER MITIGATION REQUIREMENTS

After-Hours Line Items

- Individual after-hours line items should not be used (i.e., Tear out wet non-salvage carpet, cut/bag - after business hours).
- Use only standard during business hours line items throughout the body of the estimate.

Axial 1HP Air Movers

- Axial HP blowers should not be utilized on typical water mitigation projects.
- If appropriately utilized, it must be billed as a standard ¼ HP axial fan.

Clean-Up/Final Clean

- Clean-up fees are included in the labor component of tear out line items.
- Therefore, additional hourly clean-up and cleaning line items are, in most cases, unwarranted. General vacuuming is not permitted.

CLN Items

- General cleaning of unaffected fixtures, appliances, cabinetry, walls, flooring, ceilings, windows, etc. should not be required on Category 1 and 2 mitigation losses but may be necessary in a Category 3 event.
- Additional documentation is required if these line items are utilized.

Antimicrobial

- Antimicrobial use is not permitted on Category 1 losses without prior approval by an Inside Technician, for which adequate support must be provided

Content Manipulation

- Billed by the room size.
- Hourly charges are not acceptable.

Non-Salvageable Contents

- Inventories can be typed or legibly handwritten.
- 25 unique items and under included in mitigation/contents assignment fee.
- \$125 flat fee for 26-100 unique items using line item code CDC MN Service – Minimum Charge
- Fee schedule applies to items not attempted to be cleaned; items attempted to be cleaned/repared are documented separately.
- Inventories must include descriptions, quantities, brands, and photos (e.g., 55" Samsung TV, 6' 3-cushion tan couch, 4 pairs of men's Adidas sneakers).
- Documentation uploaded in XactAnalysis for adjuster access.
- Only for vendors already assigned to content cleaning and mitigation; not for inventory-only assignments.
- No additional trip charge for correcting improper inventory collection or delivery.

Debris Removal

- Water (WTR) Xactimate category line items should be used when entering debris removal in the mitigation estimate.

Dehumidification

- Dehumidification calculations should follow the standard formula for determining the required AHAM/Pints per day requirement.
- The following standard line items (AHAM rating), Xactimate codes should be utilized.
 - WTR DHM Standard Dehumidifier with an AHAM certified rating of up to 69 pints per day.
 - WTR DHM > Large Dehumidifier with an AHAM certified rating of 70 to 109 pints per day.
 - WTR DHM >> Extra Large Dehumidifier with an AHAM certified rating of 110 to 159 pints per day.
 - WTR DHM >>> Extra Extra-Large Dehumidifier with an AHAM certified rating of 160 pints per day or greater.
- The billed item code should be based on the required AHAM rating.
 - For example, if the required AHAM is 65 pints per day and the contractor utilized a dehumidifier with a rating of 75 pints per day, the WTR DHM line-item code should be utilized for invoicing, not the WTR DHM > line-item code.
- Example:
 - Details: 800 sq. ft. of floor space within the chamber, 8-foot ceilings, class 2 loss.
 - $800 \times 8 = 6,400 \text{ CF} / 50 = 128 \text{ pints per day required.}$
 - Contractor utilized two large dehumidifiers (Dri-Eze Revolution) = 160 pints.



Allstate/Encompass/National General Program Guidelines

- Two standard sized dehumidifiers (Phoenix R125 or similar) = 130 pints.
- Contractor should bill for 2 standard dehumidifiers.

Detach & Reset Line Items

- When estimating baseboard, molding, etc. while conducting drying, the following rules should be followed:
 - CAT 1 Losses – Salvageable baseboards, molding etc.
 - WTR Detach line items should be utilized.
 - CAT 2 Losses – Detach or Remove should be utilized when materials are intended to be reset.
 - Tear out WTR line items should be utilized only when the item is not Salvageable.
 - CAT 3 Losses – Tear out WTR line items should be utilized when the item is not salvageable.
- Tear Out and Demo tasks can be found in the WTR Category and should be utilized according to Xactimate definitions, and the standards defined above.

Drying Chambers

- If multiple rooms will be considered a single Drying Chamber (Living and Dining Room, for example) and no line items will be input in one of those rooms, it is appropriate to write the second room as a sub- room of the first, so the automated audit will calculate both rooms for proper equipment placement and invoicing.

Drying Exceeding 4 Days

- If drying is to exceed four days, contact the Inside Technician to discuss alignment.
 - XactAnalysis assignment notes should be documented to confirm alignment of the mitigation being completed.
 - If contact is made on a weekend or holiday and vendor is unable to reach the Inside Technician or an Adjuster, document the XactAnalysis assignment notes to explain.
 - Note: The drying log and meter readings should support the Xactimate line items entered in the estimate.

Emergency Service Calls

- There is only one emergency service call charge per project regardless of the number of crews mobilized to the site.
- During Business Hours
 - This line item may be included on the estimate when the vendor responds to the loss within 4 hours during regular business hours.
- After-Hours
 - Assignments are considered “After Hours” if onsite arrival is before 8:00 a.m. or after 5:30 p.m. local time, Monday through Friday, on Weekends or the following holidays:
 - Memorial Day
 - July 4th
 - Labor Day
 - Thanksgiving Day
 - Christmas Day
- Exceptions to this guideline may be justified in extraordinary circumstances and only with the explicit approval from the Inside Technician.
- Documentation of the reasons for an After-Hours call should be noted in XA and identified again using an F9 note within the estimate.
- If the situation is discussed and pre-approved by the Inside Technician, the approval will be documented in the XactAnalysis assignment notes.

Service Call Only

- Vendors may be dispatched to a loss where no drying is needed. Program guidelines require the following be provided when inspection is completed and no restoration or removal is needed:
 - Photos as described in General Guidelines – to include Risk, Source, and Damage areas (including contents and building materials)
 - Moisture readings to show areas measuring at dry standard
 - Complete MICA drying logs to include all required datapoints – including Source, Category and Class of Loss, Start and Completed dates (may be the same) and mark “Service Call Only” in the MICA shell.

Allstate/Encompass/National General Program Guidelines

- Sketch of affected rooms and any additional areas where continuous flooring, ceiling or other considerations may be necessary for repairs.
 - ClaimX video must be uploaded also (use the radial button *This is a service call only. Video 1 is all that is needed*)
- Taxes may be applied to service call only estimate ONLY in the following states: Hawaii, South Dakota, New Mexico, New York, Texas, West Virginia, and Washington. All other states must remove the sales tax.

Equipment Decontamination

- CAT 3 work areas should be cleaned and disinfected prior to placing drying equipment.
- Therefore, the need for decontamination of equipment is not warranted.

Equipment Monitoring Charges

- The specific equipment used on an assignment should be based on IICRC standards. Drying charges may not be applied to the first day of drying. (Refer to Equipment Set Up.)
- Use the following guidelines for monitoring charges for drying equipment:
 - < 1,000 sq. ft. affected floor space – 1 hour
 - > 1,000 sq. ft. affected floor space – 1 * (Affected sq. ft. / 1000)
- The use of the after-hours monitoring charge will be allowed for weekend monitoring.
- Only standard line items should be used for monitoring on weekdays.
- Example:
 - Details: 1,500 sq. ft. of floor space affected, 3 days (3-24-hour periods)
 - $1,500 / 1000 = 1.5$ Hours
 - Day 1 – no monitoring fees
 - Day 2 (first 24-hour period) = 1.5 Hours
 - Day 3 (second 24-hour period) = 1.5 Hours
 - Day 4 (third 24-hour period) = 1.5 Hours
 - Total project monitoring hours = 4.5 Hours
- Minimum charge of 1 hour for less than 1,000 sq. ft.
- If monitoring is missed, please document the reason for missed days with a public note.

Equipment Set Up & Take Down

- Equipment Set Up and Take Down should be based on the amount and type of equipment utilized on the project.
- Equipment Set Up, Take Down and Monitoring charges should be billed as a total, in one line item on the estimate.
- Use the following guidelines for invoicing of equipment Set Up and Take Down.
- Example:
 - 2 dehumidifiers and 10 air movers utilized.
 - Set Up = $(2 * 15\text{min}) + (10 * 5\text{ min}) = 1\text{ hour } 20\text{ mins}$
 - Take Down = $(2 * 15\text{min}) + (10 * 5\text{ min}) = 1\text{ hour } 20\text{ mins}$

Equipment Type	Set Up Minutes	Take Down Minutes
Air Mover	5	5
Dehumidifier	15	15
Air Scrubber	5	5
Floor Drying System	15	15
Wall Cavity Drying System	15	15
Other Specialty Equipment	15	15

Flooring Removal (Also See ITTEL Guidelines)

- If carpeting cannot be saved, secure a 12" x 12" sample.
- If wood/laminate flooring cannot be saved, secure a 4" x 4" sample.
- If ceramic/vinyl tile cannot be saved, secure a sample sufficient to identify material and style.
- Providers are required to photograph the flooring to document the need for removal.
 - These pictures must include any delamination, furniture stains, chips, gouges, wood/ laminate/vinyl damage, in addition to including photos of continuous areas, transitions, etc.



Allstate/Encompass/National General Program Guidelines

- If carpet can be saved and the mitigation provider is qualified to replace pad, stretch and re-lay the carpet, this work should be completed by the mitigation provider.
 - If not qualified, it is acceptable to hire a qualified subcontractor for this task.
- Carpet pad and labor charges should be included within the mitigation provider's Xactimate estimate.
- Inside Technician approval is required prior to the removal of wood (solid or engineered), ceramic tile, and stone flooring to confirm necessity of removal and what should be done with the flooring sample.

Fogging/Deodorizing

- General fogging and/or deodorizing is not allowed on any water mitigation estimate.

HEPA Vacuuming

- Light HEPA Vac is allowed on a 'per sf' for Category 3 losses when the need for such task is appropriately documented.
- Charges should be based on the actual square footage affected by the water loss.
- XactAnalysis notes should be documented to explain when and why HEPA Vac fees are being included.

HMR Line items

- HMR line items should not be utilized on any water mitigation project.

Hourly Charges

- All billed line items must be based on that task involved and billed on the appropriate measure. Hourly charges such as content manipulation, cleaning technician and supervisory hours may not be included on any water mitigation invoice.

Labor Minimums – Mitigation

- Do not include labor minimums on mitigation estimates.

Mold

- Contact the Inside Technician/Adjuster immediately to advise of mold > 10 square feet.
- Inspection fees for mold must be approved prior to being incurred, and a copy of the 3rd party invoice should be provided and uploaded to XactAnalysis for approval.
- Limits on mold coverage may exist.
- Consult with the Inside Technician/Adjuster and customer on the remediation cost prior to the start of work.
- Remediation costs are not to be included in the mitigation estimate.

Overhead and Profit – Mitigation

- Overhead and Profit does not apply to mitigation estimates.

Personal Protective Equipment (PPE)

- PPE, such as gloves (disposable and heavy duty), full face respirators are considered tools of the trade and may not be billed.
- Replacement cartridges (PAPR) and Tyvek suits may be billed if utilized on Category 3 losses.

Pressure Washing / Steam Cleaning / Soda Blasting

- Generalized pressure washing, steam cleaning of building materials, and soda blasting are not allowed.

Significant Tear Out

- To the extent where cabinets, door casings, countertops, etc., may need to be removed, consider alternative, less invasive means to dry the property.
- Prior Inside Technician approval is needed before significant tear out is conducted.

Specialty Equipment

- When specialty equipment (any equipment other than fans or dehumidifiers) is requested/needed on the job site, document the reasoning for this equipment in the Xactimate estimate line items notes and/or XactAnalysis assignment notes.
- Pre-Approval of Specialty Equipment is required.
- Contact the Inside Technician for alignment and provide photos of the specialty equipment in place.



Allstate/Encompass/National General Program Guidelines

- If mitigation invoice includes one AFD for one day to reduce airborne particulate during demo on CAT 1 and CAT 2 losses; or one AFD for up to 2 days on a CAT 3 loss with odors; Pre-Approval is not required.
- File notes and photos should support reasons for using these items and will be considered for IT review and approval.

Tools of the Trade

- Tools of the trade include such things as thermal imaging devices, moisture meters, remote monitoring systems, work gloves, hammers, dust masks, extension cords, Tyvek suits on Cat 1 and Cat 2 losses, etc. and may not be charged.

Top-Down or In-Place Drying

- Allstate requires that all water losses to carpeted floors (excluding CAT 3 losses) include disengagement of the carpet, removal and disposal of affected cushion/pad, drying and reattachment.
- Photo documentation must be provided if the carpet tear-out line item is utilized on Category 1 and 2 losses.

WTR Category Xactimate Line Items

- When writing mitigation estimates, the proper Category to select items pertaining to water mitigation work to estimate in Xactimate is WTR.

TARPING/BOARD-UP REQUIREMENTS

Emergency Board Up

- When responding to a request for Emergency Board Up prior to an adjuster being onsite or collaborating with a vendor, it is important to notify the adjuster of any additional exposures which require immediate attention or pose additional risks to the structure (i.e., water damage, electrical hazards, contents exposure, etc.).

Emergency Service Calls

- An emergency service call should be included as a one-time charge on the estimate when the vendor responds to the loss within 4 hours during regular business hours. (TMP ESRVD)
- An after-hours emergency service call should be added as a one-time charge to the estimate if the vendor responds to the loss location after 5:30 p.m. or before 8:00 a.m. Individual after-hour line items should not be used in the estimate. (TMP ESRV)

Emergency Tarping

- When responding to a request to tarp a roof prior to the adjuster being onsite or collaborating with a vendor, it is important to note if no physical (storm) damage is observed.
- If no visible damage to shingles, ridge, vents or other roof components, coverage could be impacted, and careful consideration should be taken when completing the tarping assignment.

Overhead and Profit – Tarping/Board-Up

- Overhead and Profit does not apply to tarping/board-up estimates.

Line items in Xactimate

- All losses will be handled by Paul Davis directly – the use of a subcontractor is prohibited.
- When estimating the amount needed to reasonably secure an opening/slope, each opening/slope will need to be measured.
- Combine all opening sizes and round up to the nearest full sheet for the entire job.
- The minimum material size is 32 SF
- Use the appropriate “board-up window/door” item.
- Each individual opening size will be listed as an F9 note.
 - Example: (2) windows 3’x 5’, (1) door 2’9”x 7’, (1) wall opening 6’x 6’9” = 89.75 SF.
 - In this example, a single line item would be entered with a quantity entered as 96 SF for the entire job.
- The following line items should be used and set to the “Replace” action:
 - TMP BUP – Board-up windows and doors
 - TMP TARP – Tarp – all-purpose poly – per sq ft



Allstate/Encompass/National General Program Guidelines

FIRE MITIGATION REQUIREMENTS

Approvals

- All approvals for fire mitigation must come from IT.
- If you do not have the name of the IT Reviewer assigned to the claim, or cannot reach them, call the IT Hotline to speak with a member of their team.
 - **IT Hotline** (480-977-4880)

Corrosion Control Cleaning

- Structural items that should be considered for emergency pre-cleaning/corrosion control cleaning.
- Metallic and plastic laminate surfaces including but not limited to:
 - Plumbing faucets and fixtures
 - Metal sinks
 - Ceiling fans and light fixtures
 - Mirrors and their frames
 - Shower door frames
 - Laminate countertops
 - Window frames
 - Door hardware
 - Cabinet hardware
 - HVAC vent covers
 - HVAC components
 - Water heater components
 - Electrical panel components
 - Metal exterior doors
 - Kitchen ventilation systems
 - Built-in appliances
 - Large non-built-in appliances such as refrigerators, washers, and dryers
- After these items have been cleaned, they should be treated with an oil-based coating.
 - This will help with possible airborne smoke particles prior to full fire mitigation taking place.
- Building materials that have a high rate of salvageability but are susceptible to rapid staining/discoloration should be evaluated for emergency cleaning including but not limited to:
 - Vinyl wall coverings
 - Vinyl Floor coverings
 - Fiberglass bath fixtures

Pre-Cleaning (Thermal Fog, Protect Surfaces, Etc.)

- Pre-Cleaning shall be performed whenever appropriate.
- Rooms that should be cleaned first are kitchen and bathrooms.
- Items to consider cleaning first include marble, ceramic, ceramic tile, chrome fixtures, porcelain, stove tops, faucets, crystal, some glassware, and chrome towel bar.

Test Cleaning

- Test Cleaning is required to be performed to show the extent of the smoke/soot damage and the severity.
 - Photos of test cleaning must include the area of the test; the item tested; and a photo of the sponge/cloth used in testing.
 - Photos will support presence of soot particulate and help guide the decision regarding necessary scope of cleaning and/or repairs.
 - We will be scored annually on the accuracy of the test cleaning support provided.

ASBESTOS AND LEAD REQUIREMENTS

Asbestos Testing



Allstate/Encompass/National General Program Guidelines

- Vendors testing for asbestos will Request an Asbestos Testing Assignment via the IT Hotline, Option #4. The call handler will validate coverage, confirm pursuit of the claim, and send an Asbestos Testing Assignment to the network the mitigation vendor is working under.
- Do not contact the adjuster or claim owner, only the IT team can approve and assign Asbestos Testing job types.
- Once received, the contractor on site can be assigned, and initial testing of materials will be invoiced on this assignment.
 - If vendor is not performing the sampling and sending to the lab for testing themselves and a third-party testing company is needed, a call must be made to IT to notify.
 - If IT does not have a local testing vendor, franchise may proceed with having their testing vendor come out, but all billing must be written using Xactimate line item pricing.
 - HMR ASBT for the full survey being completed by the third party that traveled to the loss site, took the samples, and then transported them to the lab.
 - HMR ASBTPS for the number of samples tested.
 - No O&P allowed on any testing.
 - No bid items, lump sums or miscellaneous items should be submitted.
 - Correct Xactimate self-testing line items are required when franchise technicians pull samples and take them to the lab for testing.
 - HMR ASBTS is to be charged per sample being taken by the franchise and tested by the lab.
 - HMR LABH may be charged at 1 hour to account for the additional labor time.
 - Instructing the lab or third party to invoice Allstate direct is not appropriate.
 - Post Clearance Testing is to be billed on the Abatement estimate and not on the initial testing assignment.
- Required Documents for Asbestos testing- please upload the following to the Documents tab in XA
 - Chain of Custody
 - Lab Results
 - Survey/Protocol- if acquired
 - Invoices

Lead Testing

- When billing for lead testing, it should be included on the Asbestos Testing assignment.
- The Lead Testing results are required to be uploaded.
- No O&P allowed on Lead Testing and no invoices are to be billed.
- When billing for Lead Testing, use the appropriate HMR line items:
 - HMR LEADS for when self-testing is performed
 - HMR LEADPS for when a third party comes to take samples and have testing completed.
- When a third party comes out to perform the testing:
 - HMR LEAD if ONLY lead testing is performed
 - HMR BASEC if both Asbestos and Lead are being tested

Asbestos Abatement

- For assignments requiring abatement, the vendor or network will call to request an Asbestos Abatement assignment, using the IT Hotline Option #4.
- If the vendor can perform the abatement and/or provide a detailed, line-item estimate in Xactimate, complete and send it to XactAnalysis, and invoice as a specialty trade, Allstate will send the Asbestos Abatement assignment to the network.
 - Only items that should be abated are items that would be disturbed during mitigation or repairs.
 - Estimates that abate all continuous materials that are not damaged and could be encapsulated must be discussed and approved by IT prior to removal.
 - All preliminary abatement estimates must be reviewed and approved by Claims Force.
- Vendors not able to perform the work, or unable to upload a detailed estimate using Xactimate, are required to call and notify IT so they can look for a GHRN vendor. If no GHRN vendor is available, franchise may have their third-party contractor submit their estimate directly to Allstate for priority review prior to beginning the abatement. These should be submitted using the OON process, which is to email claims@claims.Allstate.com.
- Abatement of areas not impacted by the covered loss require pre-approval and documentation in support of invoicing.
- No bid items, lump sums or miscellaneous items should be submitted.



Allstate/Encompass/National General Program Guidelines

- Clearance Testing will be invoiced using Post Clearance Testing and Surveying line items in Xactimate.
 - HMR ASBTPA – Full Service Survey Base Fee – Allowed at 1
 - HMR ASBTAS – Full Service Survey Per Sample – Charged at the number of samples

CONTENTS REQUIREMENTS

Assignments & General Requirements

- All losses will be handled by Paul Davis directly – the use of a subcontractor is prohibited.
- All estimates must be written using Xactimate pricing.
- Estimates should be uploaded as preliminary in 8 days or less. Please upload supporting photos to justify from your initial walkthrough.
- **Contents assignment types:**
 - Contents Cleaning: if cleaning and packing/storing
 - Contents Packout: only when no cleaning is needed
 - Contents Other: intended for either cleaning or packout/storage when a duplicate shell exists
- Document all activity, approvals, damages and customer concerns in XactAnalysis (XA).
- If specialty vendors are needed for fine art, pianos, large clocks, electronics, etc. the adjuster or IT must be notified.
- Onsite manipulation is always preferred.

Boxed & Unboxed Items

- **Boxed**
 - Utilize the Evaluate, Pack and Inventory line item for boxing of all small items.
 - Includes the materials (box) and labor to pack each box.
 - Items should be identified and packed appropriately.
 - Boxes will be listed as Miscellaneous Items.
 - Use of Bric-a-Brac, High Density or Low Density should not be used.
 - Any deviation will require pre-approval by the adjuster during the initial scope of work.
 - Additional packing materials included by room as needed (bubble wrap for fragile items, mattress covers, moving blankets, etc.).
- **Unboxed Items**
 - Separate line items for labor to tag / wrap unboxed items included by room (disassemble beds or other furniture, apply stretch wrap, moving blankets, tagging of large items, etc.).
 - CPS LAB with a F9 note to explain the time needed.
 - The Lightweight blanket line item is to be used for if any types of moving blankets. Do not use blanket cleaning.

Business Hours Vs. After Hours

- Work will be completed during normal business hours.
- After hours or weekend work must be pre-approved by the adjuster and documented in XactAnalysis

Contents Cleaning

- The contents cleaning job assignment does not include any textiles or electronics cleaning.
- Any textile or electronics cleaning requires another assignment to the appropriate GHRN vendor- PDR is not on the vendor program for these services.
- Contents cleaning requires pre-approval.
- If approved, a separate Contents Cleaning assignment will be assigned.
- The contents should be estimated on the Contents Cleaning job type assignment and not included on the Mitigation assignment.

Cleaning

- All major items listed individually using the correct Xactimate code for cleaning.
- Heavy clean must be approved in advance by adjuster and note provided indicating reason why needed.
- Items should be identified and packed appropriately.
- Most boxes should be listed as Miscellaneous Items.
- Use of Bric-a-Brac must be approved by adjuster during scope.
- If cleaning is completed onsite, labor hours can be added by room for cleaning of small items.



Allstate/Encompass/National General Program Guidelines

- For offsite cleaning, number and type of boxes cleaned should mirror number and type of boxes on pack-out estimate.
- Any deviation should be noted on estimate.
- Line item for cleaning boxed items included per room.
- No charge for any item deemed non-restorable by vendor.
- Contact adjuster to review non-restorable items.
- Adjuster will direct vendor for salvage handling or disposal.

Deodorization

- Appropriate deodorization method should be used if needed.
- Ozone charges are billed by the CF.
- Hydroxyl Generator should be pre-approved by the adjuster and charges are per 24-hour period.
- Use should be reasonable based on volume of personal property involved.

Inventory Assignments

- If you receive an Inventory assignment, this has been sent in error. Please inform the Adjuster that they will need to engage the proper process.

Small/Moderate Inventory

- Inventories can be typed or legibly handwritten.
- 25 unique items and under included in mitigation/contents assignment fee.
- \$125 flat fee for 26-100 unique items using line item code CDC MN Service – Minimum Charge
- Fee schedule applies to items not attempted to be cleaned; items attempted to be cleaned/repared are documented separately.
- Inventories must include descriptions, quantities, brands, and photos (e.g., 55" Samsung TV, 6' 3-cushion tan couch, 4 pairs of men's Adidas sneakers).
- Documentation uploaded in XactAnalysis for adjuster access.
- Only for vendors already assigned to content cleaning and mitigation
- No additional trip charge for correcting improper inventory collection or delivery.
- If the inventory is over 100 items, please do **not** perform the inventory. We are not an approved Inventory vendor for Allstate.
 - Please call the IT or Adjuster to make them aware.

Disposal

- Disposal of personal items should not take place until a signed release of disposal has been obtained from the insured.
- Disposal should be approved by the adjuster.
- Photos should be taken of full dumpsters and uploaded to XactAnalysis.

Duplication of Service

- There will be no duplication of contents handling or manipulation across estimates when multiple job types are assigned to the same provider.

Electronics Restoration/Testing

- All electronics handling is to be referred to an Allstate approved electronics vendor- PDR is not on the vendor program for this service
- The mitigation vendor should not contact an electronics provider directly with an assignment.
- If electronics are impacted, contact the Inside Technician or Adjuster for direction.

Inspection

- Virtual collaboration should be completed with adjuster if adjuster is not onsite.
- Test cleaning should be completed by vendor on appropriate surfaces to assist adjuster in determining scope.
 - Photos of test cleaning, prior, during and after are required to be uploaded to XA.
- Factors involved in cleaning, such as availability of water and power, should be considered when determining if cleaning can be completed onsite or pack out will be needed.
- Consider moving contents within a property prior to contacting the adjuster for consideration of a pack out.
- If pack out is needed vendor should secure adjuster approval in advance and ensure approval is noted by the Adjuster in the file.



Allstate/Encompass/National General Program Guidelines

- Any specialty subcontractors (pianos/large clocks/artwork/guns/refinishers/textiles/electronics) that may be needed must be approved by adjuster and adjuster will coordinate their involvement.

Loading/Unloading & Truck Charges

- Appropriate for the size of the loss.
- Moving personal property only.
- Charges for moving employees or equipment to and from the job site are not permitted.
- Labor for loading / unloading trucks should be listed on a separate line, with quantity of hours appropriate for the items being moved.
 - 5 minutes per box
 - 15 minutes per tagged item
 - Should be billed as CPS LAB
- Labor hours for travel time are not permitted.
- Labor hours to shift items throughout the warehouse during storage are not permitted.

Organization

- Estimates should be organized by room and include ALL inventoried items.

Overhead and Profit

- Overhead and Profit does not apply to Contents estimates.

Pack Out

- Paul Davis does not discuss Pack-Out option with the Insured – this is the Adjuster’s role.
- Scope of Pack-Out and Storage will be decided by the adjuster and documented in XA notes.
 - If there is no agreed upon scope, please contact adjuster prior to packing out.
- Virtual Inspection/ClaimsXperience should be requested on every claim.
 - Once a scope with the adjuster via Virtual Inspection/Claims Experience has been approved, pack out can begin right away.
- Adjuster approval is required prior to all Pack-Out and Storage requests.
- All Pack-Out and Storage estimates must be completed using the Contents Packout assignment in XA (only when NO cleaning is needed.)
- If cleaning and packing/storing, the estimate will be completed on the Contents Cleaning assignment.
- Pack-Out should involve only personal property in affected areas where manipulation within the home is not a viable option. Please do not pack out electronics and textiles.
- Once the Pack-Out is complete, upload the estimate of work completed with supporting photo documentation.
- Requests to Pack out must be pre-approved by the Inside Technician/Adjuster.
- If approved, a separate XA assignment will likely be received for the Pack Out items.
- Be prepared to virtually collaborate and/or discuss the following:
 - Why is a Pack out needed?
 - What rooms will require pack out?
 - Why can’t contents be manipulated on site?
 - Use of on-site storage pod vs. offsite storage facility?
 - Is the pack out due to flooring replacement? If yes, what type of flooring?
 - Are there “total loss” contents items involved?

Pack-Back/Move-Back

- Pack-Back charges projected and included in the initial estimate for all Pack-Outs.
- Pack-Back charges may include a line item for labor when setting up furniture as needed.
- Allstate as a standard will not pay to unpack boxes by request of the homeowner.
- Any labor for unpacking customer items must be pre-approved by the IT and must be documented well.
- Pack-Back Labor moving hours should match with pack-out moving hours.

PODS

- PODs are billed at a monthly rental rate if approved by the adjuster for use.
- A separate drop off and pick up fee is to be included for each unit.



Allstate/Encompass/National General Program Guidelines

Scope

- Paul Davis and adjuster must agree on scope before work is started.
- Photos and estimate should follow the grouping by room.
 - Photos should be labeled appropriately.
 - Photos tab should be utilized in XA.
 - High-end items and specialty items require multiple photos of each item.
 - Photos of all items are required.
 - Photos can contain multiple items.
 - A labeled photo must be provided to support every line item in your estimate
- Climate control is the required preferred storage method.
 - Pods should only be used as a last resort and for short-term storage.
- Scope must include:
 - Grouping by room.
 - Inventory of large items and boxed inventory.
 - Clear description of all items is required.
- Boxed inventory should include general description of items in the box with photos.
 - Size and quantity of boxes involved should be recorded and photographed.
- Offsite vs. Onsite Cleaning
 - If offsite cleaning is needed, adjuster must approve pack-out.
 - If onsite cleaning, estimate of cleaning hours per room for small items.
- Vendor should utilize ContentsTrack through XactContents platform, if available.
- Any pre-existing damages should be noted and photographed prior to work.
 - Damaged items will not be removed from the home for storage unless directed by the adjuster.
- Storage should be climate controlled.
- Use of POD type units for onsite storage must be pre-approved by the adjuster.
 - Clear communication around what is stored in the POD is required with the adjuster.
 - POD type storage is not climate controlled.
 - Utilize only when environmental factors would not cause damage.
 - Staging of items.
 - Very short-term storage.
 - Non-furniture related items.

Supervisor Hours

- Supervisor hours for complex losses (losses requiring specialty operations, coordination of additional specialty vendors, etc.) only. Document the coordination needed.
- All supervisory charges require a note to explain supervisory tasks completed.
- All supervisory charges must be pre-approved and documented by the adjuster.
- Labor for supervisor performing general tasks (inventory, packing, etc.) can be billed as the standard hourly rate for the task.

Textiles

- **All** textile handling is to be referred to an Allstate approved textile vendor. We are not allowed to engage with textiles whether salvageable or non-salvageable.
- The mitigation vendor should not contact a textile provider directly with an assignment.
- If textile services are needed, notify the Inside Technician or Adjuster for the appropriate assignment routing.

Storage

- Storage charges may be supplemented after the preliminary, 8 day upload.
 - Make storage billing an open line item with a F9 note explanation.
- Storage charges of personal property charged by Square Foot (SF) per month based on volume
- Conditions: It is assumed that climate-controlled storage and pallets or vaults are used.
- Include warehouse space only.
- Billing: must include a clear date range in MM/DD/YY format
- Photo Requirement: upload photos of stored contents for adjuster review
- Labor Hours:



Allstate/Encompass/National General Program Guidelines

- Pack in/pack back labor includes warehouse handling
- Additional labor requires adjuster pre-approval and must be justified
- Vault storage: no pre-approval needed
 - Bill by SF of vault footprint using Xactimate climate-controlled SF pricing
 - Do not use per vault charges
 - SF charges for items outside vaults only

DRYWALL & TEXTURE

Acoustic Ceiling

- Damage to popcorn ceilings can be addressed in various ways, depending on amount of damage and if the ceiling has been previously painted.

Acoustic Ceiling – Spot Repairs

- This option may be used when there are prior spot repairs to the popcorn ceiling, when the existing acoustic ceiling has been painted or when the customer approves of the repair method.
- The new damage may be estimated by removing the blown acoustic, spot sealing the drywall, and replacing the blown acoustic for the damaged area only.
- The entire acoustic ceiling can then be painted to achieve a match in color.
- Floor protection is appropriate when completing this repair.
- Masking part of the wall may be considered if the damage is in close proximity to a wall.

Acoustic Ceiling – Painting Blown Acoustic

- If the only damage is a water stain to the ceiling, this option may be used when the popcorn ceiling has previously been painted or when the customer approves of the repair.

Acoustic Ceiling – Removing and Replacing Entire Blown Acoustic Ceiling

- This option may be used when the structural integrity of the blown acoustic ceiling is damaged or when there is a water stain to an unpainted blown acoustic ceiling.
- Surfaces should be sealed for proper adhesion of the new product.

Clean-Up After Drywall Operations

- Drywall line items include labor for cleanup, floor sweeping or vacuuming in the immediate workspace.
- Proper protection would eliminate the need for final cleaning.

Drywall Labor

- Frequent exceptions on drywall tasks involve the addition of drywall labor by the hour.
- Hourly labor is not generally permitted when line items exist in Xactimate for suitable estimating.
- Labor minimums will often supplement labor for smaller jobs.
-

Drywall Patch

- Drywall patch line items such as DRY PATCH and DRY PATCHLF may be appropriate; however, if multiple damage areas are present, use SF pricing and allow the labor minimum to apply appropriately.
- Consider using the item PNT PATCH for small holes, dents, nail pops etc.
- Small drywall repairs can often be done in conjunction with painting which may eliminate the need for a drywall labor minimum.

Drywall Repairs

- When replacing or repairing drywall, prepare the estimate using the actual area being repaired or patched as necessary to complete the repairs.
- When using the multiple drywall patch operations on the same estimate, verify the total drywall labor provided by individual patch operations does not exceed the amount actually necessary to complete all repairs.
- If it is a small area the drywall labor minimum will account for the additional labor.

Allstate/Encompass/National General Program Guidelines

- Since many drywall textures can be matched, the first option to consider when addressing texture after a drywall repair or a partial replacement is to blend the new texture with the existing finish.

Masking and Content Removal During Drywall or Texture Operations

- Masking of walls may be necessary when applying texture or blown acoustic.
- Floor protection, masking of cabinets etc. is appropriate at times but should be limited to the area where the repairs are taking place.
- Appropriate drywall masking/protection line items may be added with F9 notes to support.
- In general, the masking items found in the drywall categories should be the first consideration when masking to address drywall and texture repairs and/or replacement.
 - Use DRYMASK* and the like if masking is needed.
- While paint operations generally include necessary steps for protection, other operations (i.e., drywall, ceiling painting) may not.
 - Dust protection, floor protection, and the covering of some contents, including cabinets may be necessary depending on the scope of work.

PAINT

Coats of Paint

- When painting new or damaged drywall or plaster, the new/damaged area (including the float area) should include a sealer coat and two coats of paint (three total coats)
- When part of the drywall or plaster in a room is repaired or replaced, the third (finish) coat on the repaired wall or ceiling area should be extended to the undamaged walls and/or ceiling areas as necessary in order to provide a uniform appearance.
- When all the drywall or plaster in a room is replaced, the entire room should include a sealer coat and two coats of paint (three total coats).
- If walls or ceilings require painting after cleaning operations to address smoke, determine the need for sealer and the number of coats based on the results of the cleaning operations.
- Generally, interior trim components are pre-primed and PNTB should be used for baseboard that is pre-primed
 - There may be situations where trim is sold without primer and may need to be primed.
- Generally, painting bare wood requires one coat of prime and one coat of paint, while pre-prime wood (or fiberglass) would typically require one coat.
- When charging to paint both the baseboard and quarter round, use the PNT BCS line item. Charging to paint them separately is not allowed when they are the same color.
- The need for any variation, including extra coats, should be documented in F9 notes and supported through detailed and clearly-labeled photos.
- PNTSPT2 is the appropriate code for one coat of sealer and two coats of paint
- Use PNTS* and the like if priming is needed

Exterior

- When painting exterior surfaces such as siding, fences or masonry, the estimator should check the surface to ensure the repair scope addresses proper paint adhesion.
- If the surface has pre-existing dirt or mildew, there are several cleaning items in the Xactimate price list that should be considered to prepare the surface for painting.

Masking and Content Removal During Painting Operations

- The Xactimate Retail Labor Rate includes supporting events that allow time to complete operations normally completed by a painter, including moving furniture away from walls, drop and bag fixtures, and remove and reset switch plate and outlet covers.
- There is no need to include additional masking or content manipulation line items to accomplish these operations if you have included the appropriate paint line item.
- Masking of trim or openings, cut in time, and floor protection are all operations normally completed as part of the painters Retail Labor Rate and typically should not be added in addition to the paint operations.
- While paint operations generally include necessary steps for protection, other operations may not.
- Dust protection, floor protection, and the covering of some contents may be necessary depending on the scope of work.

Prep



Allstate/Encompass/National General Program Guidelines

- Painters frequently remove switch and outlet covers cover plates, drop light fixtures, and move items away from walls and make painting easier.
- An average amount of this kind of prep work is included.
- Additional prep work may be needed and will need to be documented with F9 note and clear photos.

Two Color Paint Entry

- In order to address additional labor time and inefficiencies, the two-color paint operation can be used when painting two different colors in the same room or area, in situations where accent walls and the like have a differing paint color from the rest.
- Pre-loss two color selections must be photographed to show this exists.

FLOORING

Repairs – ITEL & Flooring

- Flooring Repair/Replacement
- On Any Allstate repair assignment that you receive; Paul Davis will document, estimate, and address all damages except flooring.
- Paul Davis will refer all flooring repairs/replacements back to the claim owner/adjuster to involve CCA Global who will be utilized for all flooring repair/replacement services.
- The ITEL mobile application should still be utilized on flooring of 144 sq. ft or more.
- On Non-Complex assignments: the oversight, review and approval will be handled by the GHRN Technician (IT)
- On Complex assignments: the oversight, review and approval will be handled by the assigned coordinated adjuster.

Abandon Surfaces

- Finished surface on top of an abandon finished surface. In these situations, we would scope damage to the finished surface, not for the underlying abandon surface if it cannot be reasonably reclaimed.
- Examples:
 - Linoleum sheet good glued down to an old linoleum floor is an example where we should only address the one finished surface of linoleum as it is not reasonable to expect the first layer to be reused as a finished surface.
 - Carpet over hardwood in an example of when we would consider both the carpet and any damages to the hardwood floor. Generally, only a seal coat and not stain since the floor would most likely need refinished if the homeowner decided to reclaim the hardwood as the finished surface. Adjuster approval should be documented in XactAnalysis notes prior to upload.

Carpet Direction

- It is recommended that machine direction of the carpet be installed in the length direction of the stairs.
- Most manufacturers recommend carpet pile direction run down the stairs.

Carpet Pad

- Since carpet pad can typically be matched, replacing only the damaged pad should be considered the first option.
- The need to replace additional pad beyond the damaged area should be addressed in XactAnalysis assignment notes with photos to support.

Dust Protection

- When sanding hardwood flooring, it may be necessary to seal openings to prevent the spread of dust into undamaged areas of the home.

Dustless Sanding

- Dustless sanding is permitted and reduces the need for additional dust control or final cleaning in the most cases.
 - Cabinet masking may be needed when sanding a kitchen to reduce micro-dust inside the cabinets.
 - F9 note required.
- The dustless sanding operation may be used when a truck or trailer mounted equipment is utilized, which would reduce the need for additional dust control in many cases.

Flooring Measurement

- When estimating carpet or sheet vinyl flooring, the roll out method in Xactimate should be used. This should be done in sketch using the flooring orientation tool.



Allstate/Encompass/National General Program Guidelines

Floor Protection

- When salvageable or new flooring needs to be protected, always take into consideration how much protection is needed.

ITEL

- ITEL is required on all carpet, vinyl and laminate/wood flooring to support anything over Standard Grade.
- On all flooring replacements over 144 square feet, ITEL must be used.
- Mobile App preferred, however if mobile app not available please submit physical sample of flooring using the "Expedited Service".
- If waiting on an ITEL, use Spec for Independent Analysis line item and leave material price open until ITEL returns.
- When using the mobile app, a Same Day response should be requested unless the adjuster specifically requests otherwise.
- XactAnalysis notes should be updated to show ITEL has been submitted.
- ITEL results should be uploaded and attached as a document in XactAnalysis.
- Please see below Cabinetry section regarding new policy on ITEL kitchen cabinet analysis.

Graphical Estimating

- All carpet and vinyl replacements must be estimated using the "Roll Out Method" in sketch.
- Flooring Orientation and Carpet Pattern – use the direction with the most efficiency (least waste) and appropriate seaming.

Hardwood Refinish

- No need to remove baseboard.

Multiple Layers

- When a finished floor is found under another floor, you MUST reach out to the adjuster or IT for guidance on how to handle multiple floors and document XA with who you spoke with and your next steps.
- Example: hardwood under carpet.

Pile Direction

- Where two or more pieces of the same broadloom carpet are adjacent, the pile direction is required to be the same unless otherwise specified.
- Uniform pile direction is not required with dissimilar carpet.
- Ideally, install carpet with the pile lay toward the entrances, but other factors such as pattern, aesthetics, and economic use of material may be considered.

Seams

- Keep seams to a minimum.
- When possible, position seams so that:
 - Seams should run the length of the area.
 - Main traffic should run parallel to, rather than across, the seam.
 - Natural light does not strike across the seam.
 - Seams are away from areas subjected to pivoting traffic.
 - Seams are not perpendicular to doorway openings.

Xactimate Flooring Settings

- The following Xactimate settings should be utilized in flooring estimates:
 - Max Fill Pieces: 2
 - Minimum Fill Cut Length: 2'
 - Minimum Fill Cut Width: 2'
 - Roll Length Overcut: 3"
 - Seam Allowance Overcut: 3"
 - Stair Overcut: 0"
 - Use Scrap: Yes – check box



Allstate/Encompass/National General Program Guidelines

GENERAL RECONSTRUCTION REQUIREMENTS

Estimate Only Fee

- **Non complex assignments-** The purpose of a non-complex assignment is for vendors to assess property damages and prepare an estimate reflecting their bid to complete the repairs. If the vendor is unsuccessful in securing the job, they will not be compensated for preparing the estimate except if you have had no opportunity to sell your services (e.g., the homeowner had already secured a contractor before your involvement). In such cases, the office **must contact the GHRN Inside Technician assigned to the file for estimate fee approval.**

Estimate Scoping Assignments

- **The purpose of an estimate scoping assignment is for the office to provide a repair cost assessment on claims without the expectation of securing the job. You are eligible to charge a fee for this service only if there is a documented schedule between Allstate and the office. Occasionally, estimate scoping assignments may turn into sold jobs. If this occurs, the office will no longer be eligible to charge an estimate fee for that assignment.**

Supporting Your Scope

- A labeled photo must be provided to support every line item in your estimate.
- O&P must be clearly supported through written commentary for every estimate it is applied to.
- Pre-approvals must be clearly documented in line-item notes for all scope that requires pre-approval.
- Reconstruction estimates cannot be QA Approved until:
 - Validate Prescrub (Instant Review & Revisions) is completed before upload to XactAnalysis.
 - All required supporting documents are uploaded.
 - Adequate commentary is included in estimate, 24-hour report, and XactAnalysis notes.
 - If full-service, the mitigation estimate is fully reconciled and QA Approved
 - This prevents overlap with the mit scope and ensures that scope of work and quantities match.

Building Code

- Prior to adding any code item, it is the estimator's responsibility to verify the local code requirements and those requirements will be enforced during the repair of the covered loss.
- If unsure, the estimate can be documented to indicate building code costs will be included once they are determined. The line items associated with building code should be coded to the building code coverage within the Xactimate estimate.
- Contact the Inside Technician or Adjuster for direction should any building code requirements need to be addressed in the estimate, and to discuss availability of Building Code coverage on the policy.

Building Permits/Fees

- Building permits and fees should be paid on an incurred basis unless the amount is known at the time the estimate is being prepared.
- Leave this as an open item on the estimate until the incurred fees are determined. An appropriate narrative should be added to the estimate line item.
- As incurred, permit and fee invoices should be attached in XactAnalysis.

Cabinetry

- Allstate has specialty vendors for cabinetry that may be engaged in a job. Please inquire with the IT team on if there is going to be a specific vendor used just for the cabinets or if your team should continue to estimate for these repairs.
- New requirement as of 3/31/25 regarding physically damaged kitchen cabinetry: the itel Now Mobile App Cabinet Repair Analysis should be used when kitchen cabinets only are damaged, *except* when there is only damage to the toe kick. If cabinets are a total loss, no app submission is needed, however please ensure you still follow the process of notifying the IT.
 - Please note Allstate will allow the use of (CON-ROOM) if contents manipulation is needed when the Cabinet Repair Analysis is completed. Please ensure you have appropriate photo support as well.
 - Please review the training in the MS TEAMS channel for further details.

Comb and Straighten Air Conditioning (AC) Fins



Allstate/Encompass/National General Program Guidelines

- When combing and straightening AC fins on one AC unit, it is acceptable to allow the entry to comb/straighten fins with a trip charge.
- When two units involved, include one entry to comb/straighten fins with a trip charge and one without.

Debris Removal

- If the debris from the repair of a covered loss can be placed into an on-site trash receptacle such as a trash can, there is no need to add this item to the estimate.
- Do not leave the debris in the on-site trash can.
- When the debris cannot fit into a trash can, but is not significant enough to warrant a dumpster, it is recommended to use "Haul debris - per pickup truck load - including dump fees".
- If a full load is not required, quantities should be adjusted accordingly (i.e., qty .25, .50, .75 of a full load).
- Line item used would be based on volume and/or weight of items being disposed of
- Fees include use of pickup/dump trailer, Dumping/transfer fees and labor.

Demolition

- When estimating to selectively remove individual damaged items, the Xactimate removal or remove/replace line item should be used.
- If estimating the removal of all components of a room, the Xactimate demolish/remove room line items should be used.
- If estimating the demolition of an entire structure, the demolish/remove home may be appropriate.
- Document the Notes in XactAnalysis if there is any deviation from this standard.

Depreciation

- When applicable, depreciation should be input by line item based on market laws and regulations.
- When directed by the Inside Technician or Adjuster, depreciation should be noted on the estimate, even in cases where the initial payment is based on replacement cost value.
- If the Inside Technician or Adjuster does not provide direction for depreciation in the XactAnalysis Notes, the service provider should not apply depreciation to their uploaded estimate.
- No "blanket" depreciation.

Fencing

- When addressing damages to fencing, repairs will be the first option wherever practical.

Final Clean

- Generally speaking, many Xactimate line items include time for clean up after the operation is completed.
- As a result, the final clean line item should not be required on most estimates.
- If the scope of the covered loss requires the addition of the final clean item, an XactAnalysis assignment note explaining the circumstance should be included.

Labor Minimums

- A Labor Minimum represents the minimum amount of labor dollars necessary to perform repairs or replacement work on a job if a sub-contractor for that trade were to perform the work.
- As a result, the estimator needs to determine which Labor Minimums are appropriate based upon the repairs and trades people necessary for the repairs.
- The estimator should evaluate the complete list of labor minimums generated by Xactimate and determine if each is required before finalizing the estimate.
- Only skilled trades mobilized should have labor minimums apply.
- For example, we should not apply an insulation labor minimum as the drywall tradesperson could install the insulation.

Lead Paint Safety Wording

- Lead paint safety wording should be applied to estimates prepared on loss locations built in 1978 and earlier, which involve painting and repainting, or destructive tear out and replacement of painted materials.
- Payment for this charge will be on an incurred basis with a copy of the testing results being attached in XactAnalysis.
- The estimate item to be utilized in Xactimate is Category: HMR, Selector: LEADS.
- When entering this item, it should be billed as part of the Asbestos Testing Assignment.



Allstate/Encompass/National General Program Guidelines

Line-Item Overrides

- Xactimate is the GHRN standard estimating system, and the values calculated should not need to be edited in most situations.
- If it is determined that a material price or labor cost needs to be adjusted for a specific loss, a line-item price override may be made by changing the material price, retail labor rate, or both in the “Component” section of the Line Items tab in the estimate.
- Do not use the Market Conditions option.
- Any changes in Xactimate pricing must be documented in the line item or in the XactAnalysis assignment Notes.

Overhead and Profit – Reconstruction

- Overhead and Profit is not guaranteed on a reconstruction assignment.
- If you have support and believe that overhead and profit is warranted on your assignment, you must explain in as much detail as possible, the complexity and coordination.
- To properly demonstrate complexity and coordination, consider the following:
 - To obtain approval to include O&P, please provide adequate support to demonstrate the complexity of repairs and need for coordination in a note in XactAnalysis.
 - This can include but is not limited to attaching schedules (available through RMS) and timesheets, providing additional written details regarding the trades required, and collaboration, coordination, and communication required to complete the job.
 - These documents must be uploaded to XactAnalysis.
- If an Adjuster writes the estimate, do not add O&P to the estimate unless you have prior approval.
 - You will need to state who granted the approval in your notes.
- Allstate will not pay for O&P on assignments where there is an obvious lack of complexity and coordination; therefore, do not request O&P on such assignments.
- As a reminder, do not discuss your estimate or O&P with the customer until it has been approved by Allstate; these types of communications should be internal only.
- All employees must be aware of the O&P guidelines.

Removing Sinks/Faucets

- Need to ensure you are checking the line-item details and uploading clear photos of work needing to be done.
- A straight stop and/or angle stop may be required to be removed to facilitate the removal of a cabinet too.
- Water lines may even need to be capped for the same reasons as above.
- In many cases the shut-off valve will not shut-off and in order to not create additional damages the vendor may cap the line or add a new angle stop after the removal was completed.
- (PLM CAPC+) F9 note should be added to explain capping the line or adding a new angle stop.
- Cultured marble countertops with a built-in incorporated sink do not include the p-trap in its pricing.
 - The definition is different than a single bowl sink (MBL_VTSNK).

RVT

- The Xactimate Residential Valuation Tool (RVT) is not to be used by GHRN contractors.
- Contact the Adjuster/Inside Technician for direction on how to proceed.

Siding

- Since most Xactimate siding options include the average time necessary for normal applications with a platform not exceeding 20', scaffolding should be considered when replacing siding when the elevation height is greater than or equal to 26 feet.
- The replacement of insulation behind siding should be based on the damages/specific repairs as it is not required in all circumstances.
- When estimating vinyl siding costs, please follow the process that includes specific program details under the siding line item in Xactimate. CF will not approve or collaborate on the estimate if it lacks the correct pricing and line-item verbiage.

Allstate/Encompass/National General Program Guidelines

SDGVINYL	Siding - vinyl
SDGVINYL+	Siding - vinyl - High grade
SDGVINYL++	Siding - vinyl - Premium grade
SDGVINBB	Siding - vinyl - board & batten
SDGVINYLI	Siding - vinyl - insulated

Vanities

- If the vanity did not have an open back (and a hole was drilled for a 1.5" inch ABS plumbing line in the back of the cabinet to feed the sink) it would be necessary to disassemble the p-trap to facilitate the removal of the cabinet/vanity.
- Removing and resetting of the p-trap would be needed.
- (PLM SNKRS+) F9 note should be added to the estimate to explain.

ROOFING REQUIREMENTS

2 Story Charges

- The 2nd story (Height) allowance should be applied when the eave of the slope is 14 feet or greater above grade.
- Charge to be applied to entire facet/slope if a portion of the facet/slope eave is 14 feet or greater above grade.
- Allowances for additional safety measures and loss of productivity are included in this Xactimate operation.
 - Example: A simple gable house that is one story slope facing the street and two stories at the rear.
 - The rear facing slope should have the 2nd story (Height) allowance since that eave is 2 stories above grade.
 - No allowance necessary for the front facing slope.
 - Direct access from one level to the next has no impact on this charge.

20 Year 3-Tab Shingles

- The availability of 20 year 3-tab shingle can be limited in some markets.
- If in question, availability of the material can be confirmed by checking shingle manufacturer websites, contacting a roof material wholesaler, or by reviewing with a reliable source.
- If a 20 year 3-tab shingle is not available in a specific market, a 25 year 3-tab shingle can be used to complete individual shingle repair or slope/roof replacements.
- XactAnalysis notes should be documented accordingly.

Decking - Spaced or Gaps

- If spaced or gapped decking is exposed due to the removal of the existing layer(s) of shingles, the estimate should provide to put the roof back in its pre-existing condition.
- As a result, the estimate should allow to re-install the new shingles over the existing decking.
- Contact the Inside Technician or Adjuster for direction if the decking needs to be addressed due to building code issues, and availability of Building Code coverage on the policy.
 - Example: If one of the underlying layers needing to be removed in the course of the replacement is a wood shingle layer, the estimate should address the gaps in the decking since the wood shingles that were removed were acting as a nailing surface for the top layer of shingles.
 - In general, the gapped or spaced decking in this situation can be addressed by overlaying the existing decking with new plywood or OSB sheets.

Drip Edge/Gutter Apron

- When replacing a roof or a slope which has drip edge, allow for the removal and replacement of the drip edge as the Xactimate system doesn't distinguish that it is included in the removal of the roof.
- When addressing gutter apron, one should verify the attachment points for the apron to determine if it needs to be removed when replacing the roof.
- If it is necessary to remove the apron or if the apron was damaged in the covered loss, include the removal and replacement of the apron in your estimate.



Allstate/Encompass/National General Program Guidelines

- Contact the Inside Technician or Adjuster for instruction if drip edge is required to meet building code requirements and availability of Building Code coverage on the policy.

EagleView

- The estimator should review the EagleView diagram in order to verify all slopes have been included in the report and no changes have been made to the roof system since the EagleView photo was taken.
- Any slopes or gable returns not included in the EagleView diagram should be added into the Xactimate estimate.

Exhaust Vents

- Since exhaust vents/caps are typically connected to duct work or PVC piping within the attic, they are not removed with the shingles and need to be removed/replaced or removed/reset, depending on whether they exhibit loss related damage.
- Removal component use is intended to be used when only the exhaust vent is being removed for disposal.
- If the vent is being removed along with the shingles on the same roof slope, the vent removal would generally be included with the shingle removal line item.

Ice and Water Shield

- When a portion of the existing roof contains ice and water shield, the appropriate amount of ice and water shield should be added to the estimate.
- Since it is not common for felt to be installed over ice and water shield, one should deduct the quantity of ice and water shield from the amount of felt paper required in the estimate.
- Contact the Inside Technician or Adjuster for instruction if ice and water shield is required to meet building code requirements and availability of Building Code coverage on the policy.
- To determine the amount of ice and water shield needed to comply with building codes, use the Ice and Water Calculator.

Flashings

- Flashings should be replaced if they exhibit loss related damages.
- If the flashings are not damaged in the loss, the first option is to consider re-using the flashings without replacement.

Painting of Drip Edge, Vents and Gutters

- Gutters/downspouts, vents and drip edge are available in a wide variety of Colors and should only be painted if the original items were painted a unique color which is not available from the manufacturer.

Pipe Jack Flashings

- When replacing a roof or slope that contains pipe jack flashing, the removal of the pipe jack is included with the removal of the shingles.
- Pipe jack flashing should be replaced if they exhibit loss related damages.
- If the flashings are not damaged in the loss, the first option is to consider removing and reinstalling the flashings.
- If the removal and installation of the flashing cannot be completed based on their pre-existing condition, the flashings should be replaced.

Powered Roof Vents

- When addressing damages to powered roof vent, the replacement of the power vent cover only should be the first consideration.
- Undamaged Powered roof vents and covers typically do not need to be removed and reset to replace the roof.
- If this operation is needed, document file circumstances and provide photos as support.

Rain Diverters

- When replacing a roof or a slope, the removal of rain diverters installed over the shingles should take place during the shingle removal.
- As a result, an additional removal charge is not typically needed.

Removal of Layers

- When allowing for the replacement of a roof or slope after a covered loss, the removal of all existing layers of roofing material is acceptable.
- However, this may not apply when a roof is installed on a batten system and not nailed into the sublayer.



Allstate/Encompass/National General Program Guidelines

- Photos and/or documentation must support additional layers.

Removal of Ridge

- When replacing an entire roof, the removal of the ridge shingles will be completed with the removal of the slopes.
- As a result, no additional allowance needs to be made for the removal of the ridge shingles.
- When replacing an individual slope, additional care needs to be taken in the removal of the ridge shingles as not to damage the slope(s) that will remain.
- As such, the removal of the ridge shingles should be included when replacing individual slopes.

Roof Mounted Evaporative (Swamp) Coolers

- When estimating to replace a roof with a roof mounted swamp cooler or air conditioner, add up to 3 hours of roofer's labor (RFG LAB) to lift and work around unit.
- Any deviations will be handled on a case-by-case basis and should be clearly documented in the XactAnalysis assignment notes and supported with photos.

Satellite Dish Alignment

- If the satellite dish is mounted on the roof or otherwise needs to be removed and reset to facilitate the replacement of the roof, the removal and resetting of the satellite dish should be included in the estimate.
- Generally, the realignment of the dish should only be included when the realignment expense is incurred.
- Contact the Inside Technician or Adjuster for guidance regarding realignment of satellite dish(s).

Shingle and Felt Estimate Items

- Shingles and felt entries should be added separately due to the different waste requirements for each item.
- The combined felt/shingle line item can be used for removal.

Solar Panels

- When solar panels are involved in a covered loss, a discussion should take place with the Inside Technician or Adjuster for instruction.
- If panels are leased, there may be strict requirements for leasing company to handle the panels.

Steep Charges on Repairs

- Steep charges on roof repairs can be addressed by adding roofing labor hours to address reduced efficiency or by adding the steep charge line item calculated on the number of shingles being replaced.
- In either case, the total steep charges should be reviewed to verify it accurately addresses the expense/time needed for the work.

Tarps

- If tarping is required, Xactimate tarping line items should be included in the estimate.

Valley Shingles

- When estimating to remove and replace valley metal when not replacing the slope(s), use remove and replace individual shingles to estimate for the shingles on either side of the valley.

Vent Replacement

- When replacing a roof or slope which contains vents, the removal of the vents is typically included with the removal of the shingles.
- Check the Xactimate definition for confirmation that vent removal is included with shingle removal.
- If the vents did not sustain damage from the covered peril and can be re-installed, detach and reset of the vents should be included in the estimate by allowing the detach/reset (r) action within the appropriate vent line item.
- If the vents were damaged in the covered loss, the estimate should contain an entry to replace the vents.
- When replacing a vent on a slope where the roof is not being replaced, the vent replacement entry includes labor to manipulate shingles for the installation of the new vent.

Waste on Roofing

- The roof waste calculator should be utilized to determine the amount of waste to be added to a shingled roof.
- There is no need to add waste to felt.



Allstate/Encompass/National General Program Guidelines

- Since both steep and 2 story charges are added to address labor inefficiencies, the actual area of the roof (not including waste) should be used when adding either of these charges to an estimate.

TREE & TREE DEBRIS REMOVAL

Tree and Tree Debris Removal

- In general, the removal of tree debris from the Allstate customer's damaged structure(s) to the ground, to perform repairs should be estimated as part of the covered repair.
- Once the tree is removed to the ground, there may be a limit to remove the tree debris from the premises.
- The line items associated with this debris removal from the premises should be coded to the appropriate coverage in the estimate.
- Contact the Inside Technician or Adjuster to discuss any potential limitations for tree and tree debris removal.

ICE DAMS & WINTERIZATION

Ice Dams

- Do not remove, or recommend to the insured that they remove, snow/ice from the roof.
 - This activity creates a potentially dangerous situation, and we don't want to put anyone at risk.
 - If a customer asks about removing ice/snow, please recommend against it and document the file with your conversation.
- A Network Contractor should not be assigned to remove snow/ice from a roof.
 - If you see such instructions in a claim:
 - Do not perform this snow/ice removal work.
 - Contact the IT/Adjuster to let them know.
- You must upload photos to support what is being billed for.
 - When in doubt, contact the IT/Adjuster, document the file, and take detailed photos.
- Mitigation Contractors
 - Please remember that we generally do not want to set up drying equipment until the source of the leak is completely thawed and stopped.
 - If you are able to channel a leak into a bucket or a drain, or away from the structure, or if you can otherwise prevent the ongoing leak from further damaging materials, then it is OK to begin drying.
 - Otherwise, do not begin drying until the ice dam has melted and leak has stopped.
- Contents typically are not covered on Allstate claims when damaged because of an ice dam.
- Discuss with the IT/adjuster if issues arise.

Winterization

- Each winter through spring, efforts needed to winterize the home should be part of an Emergency Service on every claim where heat is off (unless it is a total loss) and it must be completed properly.
- Networks are expected to drain water heaters, radiators, blow out lines, etc., when this is necessary.

ESTIMATE FEE SCHEDULE

- Included in the fee schedule: office and clerical expenses and travel within reported territory coverage
- Not Included: mileage exceeding reported territory coverage
- Xactanalysis job type is Estimate/Scoping Only
- Fee based on Allstate approved estimate amount in Xactanalysis
- Estimates are reviewed by PDRI Claims Force team
- Required documentation: sketch, labeled photos, explanation of loss in public note
- Mistaken assignment- sent to PDR in error and a site inspection has been performed but no estimate written
 - Requirements:
 - Labeled inspection photos
 - Correct line item to use- FEE EMOB



Allstate/Encompass/National General Program Guidelines

CLAIM RANGE	FEE
Mold Estimate	These charges should be the same as the repair estimate fee.
Mistaken Assignment (assigned in error by client), claim withdrawn after visit	\$75
Estimate Only Fee Schedule:	
\$0.01 -\$5,000.00	\$250.00
\$5,000.01-\$10,000	\$300.00
\$10,000.01-\$15,000.00	\$350.00
\$15,000.01-\$25,000.00	\$400.00
\$25,000.01-\$50,000.00	\$450.00
\$50,000.00 and up	1.0%, but not less than \$500

DOCUMENTATION REQUIREMENTS

MICA Mobility

- MICA Mobility is required to be used on all Allstate mitigation assignments.
- All Mitigation – Water and Mitigation – Other assignments in XactAnalysis (related to a water peril) will require the use of MICA Mobility for recording Job Information related (but not limited) to:
 - Contact and inspection dates and times
 - Category, Class and source of water
 - Equipment set up, takedown and monitoring.
 - Drying Logs
 - Temperature/Humidity readings inside/outside as well as the air going into and out of the dehumidifier.
 - Grains per pound as well as grain depression
 - Equipment utilization should be properly reflected to the nearest tenth of a day in Xactimate.
 - The type of meters used to determine moisture content.
 - Daily readings from dehumidifiers
 - Drying goal (percent or pints) of affected materials
 - Completion of onsite mitigation services
- Any assignments uploaded without MICA Mobility API data will not be reviewed by Claims Force until reconciled.

MICA Details Report

- The Details Report is the drying document within MICA that the Claims Force Team and Allstate uses to review the claim.
- Whenever you have made changes to your drying logs and/or added any new photos in MICA a new Details Report should be created.
- How to Create a Details Report in MICA
 3. In the MICA assignment navigate to Reports tab located in the blue ribbon.
 4. Click on Create Detail Report

Work Authorization and Certificate of Completion

Updated July 1, 2026



Allstate/Encompass/National General Program Guidelines

- Work authorization must be signed and dated before starting work.
- Certificate of Completion must be signed and dated after work is complete.
- Combination WA/CoC is allowed.
- Submission to carrier not allowed without either document.
- If insured is unavailable for signature, contact carrier.

Photographs

- Please ensure you do not upload an excessive amount of photos. The photos should be relevant and tell the story of the loss.
 - For example, photos of moisture readings are not required

Photo Required	Label Photo	Example	Description
Front of Risk	Front of Risk	Front of Risk	Front of home to show house numbers if possible.
Initial Inspection	Initial + Room Name + Surfaces Damaged	Initial - Kitchen - Wood floor and cabinet	Take at least one photo of each room damaged-providing overview of the damage areas as seen upon initial inspection; including impacted room, the types of surfaces affected, damage and any personal property manipulation required.
Source of Loss	Source of Loss	Source - Supply Line - Kitchen Sink	Item that failed/caused the damage (supply line, fitting, electrical components, toilet/tub/sink, appliance, etc.).
Demo and Removals	Demo + Room + Material	Demo - Kitchen - Base trim	Identify surfaces removed, including photo of the material for proper identification and location of demo within the room.
Bagged for Disposal	Bagged + Material	Bagged Vinyl Flooring	Materials bagged for disposal will not be approved if no photos to support line items used in the estimate.
Equipment	Type of Equipment + Room	Lg Dehu - Kitchen	All dehumidification equipment utilized, including close ups that identify the model used (i.e. Evolution, 200MAX), specialty equipment, and debris to support line items in the estimate.
Completed Work	Final + Room	Final - Kitchen	Photos show final view of all demo, drying and mitigation. Overview of each room should show location of demo and removals for proper scope of reconstruction estimate.
Continuous Areas	Continuous + Material + Room	Continuous - Wood floor - Hallway	Identify areas not damaged containing the same material with no natural break (flooring, wallcovering, texture, paint, etc.). Photos should show transitions at doorway, continuous trim, wall and ceiling surfaces with no natural break.

Allstate/Encompass/National General Program Guidelines

Pre-Existing Damages	Pre-Existing + Room + Damage	Pre-Existing - Kitchen - Pet damage	Identify damage not related to the loss and provide support for potential claims against vendor.
Subrogation Evidence	Subro + Item + Details	Subro - Refrigerator - Make, Model, Serial#	Provide photo of the failed part/cause of loss and any manufacturer, model #, serial #, etc. for subrogation. Save all parts for adjuster to provide direction. Example: Photos of refrigerator, the icemaker line, and the Make/Model/Serial # of refrigerator (3 photos).
Roofing - Additional Layers	Roofing + Additional Layers	Roofing - 2 layers	Provide close up of roofing at edge to show multiple layers of materials.
Supplements	Supplement + Room + Material	Supplement - Laundry - Underlayment	Photos are required to support missed damage and additional items following initial upload.

*****Proper photos should tell the story and provide support for initial state of the home and final completion of work.**

Subcontractor Invoices/Bids

- If a specialty subcontractor is required, obtain adjuster approval and upload their invoice as a PDF document.
- Sub bid cannot be a lump sum but must be detailed in scope and pricing.

Xactimate Sketch

- Xactimate Sketch tool must be used to dimension all affected rooms and represent the floor layout (not separate rooms).
- Measurements required for openings, deductions and reference blocks.
- Sketch all rooms/roofs/areas as appropriate for the loss.
- All measurements are to be within 1" of actual dimensions.
- Openings and Obstructions: All openings (windows, doors, and pass-throughs) and obstructions around damage should be included within the Xactimate sketch.
 - Your Xactimate settings should be set to default to "Deduct if >0.00 SF" on all doors, windows and openings.
 - Large obstructions such as rows of cabinetry should also be depicted on Xactimate sketches.
- Xactimate defaults generally deduct square footage of wall, ceiling and floor areas behind reference block areas.
- If there is a need to clean/paint/install items within a reference block area, change the default setting within the individual estimate and provide an F9 note with an explanation.
- When possible, reference areas should be utilized to demonstrate moisture mapping within the area(s) of damage.
- Utilize separate levels to differentiate multiple floors of property.
- Distance from floor to ceiling must be measured to the nearest inch, including sloped, standard and clerestory structures.
- Measure floor area by measuring finished wall to finished wall.
- Window/Door openings should be measured to the outside edge of the trim.
- On short walls where sketch will not allow the door opening to be placed when measuring to the outside edge of the trim, measure to the inside edge of the trim.
- Closets should be included as a sub-room in Xactimate if the scope of damage matches the scope of damage in the corresponding room. When the scope of repairs differs from the corresponding room, the closet can be considered a separate room.
 - However, flooring quantities should be reviewed for accuracy given that carpet waste from the corresponding room can often be used in the closet area.
- All door and window openings must be included in the sketch, regardless of size.



Allstate/Encompass/National General Program Guidelines

- When estimating carpet or sheet vinyl flooring, the roll out method in Xactimate should be used.
 - This should be done in sketch using the flooring orientation tool.
- Xactimate defaults generally deduct square footage of wall, ceiling and floor areas behind reference block areas.
 - If there is a need to clean/paint/install items within a reference block area, change the default setting within the individual estimate.

CF REVIEW CHECKLIST

CF Review Checklist

- Photos uploaded into XactAnalysis Photos tab and properly labeled per GHRN Standards
- Sketch uploaded into XactAnalysis as a connected floorplan with all windows, doors, tubs, showers, fireplaces, cabinets, etc. identified as reference blocks or openings.
- Proper set up of estimate to include estimate header, estimator's name and contact information, Price List in Xactimate, measurements in each room and appropriate sales tax.
- Depreciation and deductible applied on the estimate, if requested by the adjuster
- Review estimate for any tasks not compliant with estimating standards:
 - Hourly Labor charges
 - Contents Manipulation by the hour
 - Debris removal – size of truck/dumpster appropriate for quantity of debris (partial truck for smaller losses)
- Estimator's notes (F9 Notes) added where pre-approval or explanation is required.
- If Mitigation Estimate:
 - Review non-WTR codes within Xactimate for appropriateness.
 - Tear Out on Category 1 losses – vs. detach or remove.
 - Validate ESTM Calculations
 - Proper Emergency Service Call coding (During or After Hours)
 - Remove unnecessary labor minimums.
- If Reconstruction estimate:
 - If flooring is involved, was appropriate type and grade of materials used; and if Carpet or Vinyl – was roll out method used?
 - Paint Operations for number of coats and any excess mask, protect or detach and reset of plates and fixtures?
 - Final Clean is generally not warranted – if included, are photos and F9 notes adequate to support.
 - Remove unnecessary labor minimums.
 - Overhead and Profit – does complexity and coordination warrant additional O&P?

Duplication of Tasks - Overlap Between Mitigation & Reconstruction Estimates

- When completing an estimate for a structural repair after mitigation work has been completed, the estimator should review the mitigation estimate and/or review scope of work to be performed with the Inside Technician or Adjuster.
- This will allow the estimator to avoid overlap or duplication of items already addressed by mitigation, including but not limited to: Detach and reset items, removals, debris removed, sealing and cleaning charges, etc.
- Please note that PDRI CF cannot approve a reconstruction estimate on a full-service job if the mitigation estimate has not been fully supported and reconciled through the Validate review process with a QA Approval.

Proper Documentation - Not utilizing F9 notes when deviating from estimating standards.

- Most exceptions called could be avoided if photos and documentation from vendor are in XA.
- Not requesting approvals from Claim owner/IT when appropriate